

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
H. Rein "A" No. 4.

SEC. 27 T. 14 R. 13W
CSL NW SW
990' S 660' E W $\frac{1}{4}$ Cor.

Total Depth. 2915'
Comm. 10-6-40 Comp. 10-20-40
Shot or Treated.
Contractor.
Issued. 11-30-40

County. Russell



CASING:
10 $\frac{3}{4}$ " 381'
6" 2890'

Elevation.

Production. Pot. 891.09 B.,
no wtr, Phy.
Figures Indicate Bottom of Formations.

shale	110
shale sdy	120
shale & shells	220
sand	234
shale sand	380
shale	390
shale & shells	645
shale	678
anhydrite lime	718
shale & shells	1140
salt shale	1330
shale & shells	1530
lime	1570
shale & lime	1595
shale & shells	1630
lime	1650
lime brkn	1713
shale & lime	1820
shale & shells	1832
lime	1865
shale & lime shells	1917
shale & lime	2044
shale & shells	2168
shale & lime shells	2306
shale & shells	2370
shale & lime	2650
lime	2788
shale & lime	2858
shale	2861
lime	2915
Total Depth.	

Top of K.C. lime from
cement floor level 2859
Total Depth from cement
floor level 2914
Total fillup w/oil 900'
10-21-40 acidized w/1000 Gals.
10-22-40 acidized w/7000 Gals.
10-25-40 on initial physical
potential test the well pumped
297.03 BO in 8 hrs, giving the
well a 24-hr potential test of
891.09 BO, no wtr - Daily
allowable 18 Bbls, based on
1.01% & 20-acre spacing