

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - W. H. BLACK
Farm - Sherwood

No. 1

SEC. 28 T. 14 R. 13W
SW NW NW

Total Depth. 3169

Comm. 6-17-49

Comp. 6-26-49


Shot or Treated. acid

Contractor. W. H. Black

Issued. 9-17-49

County. Russell.

KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 405 cem. w/200 sx.
5 1/2" 3165 cem. w/200 sx.

Figures Indicate Bottom of Formations.

sand, post rock & shale	164
shale & shells	180
iron, sand & shale	375
shale & shells	390
red bed	405
red bed & shale	570
red bed	705
anhyd.	740
red bed & shale	840
shale & shells	1095
salt	1380
lime, shale & shells	1430
shale & lime	1575
lime & shale	1700
lime	1870
shale & lime	2595
lime	3169
Total Depth	
Tops;	
anhyd.	705
Tarkio	2251
Topeka	2592
Kansas City	2886
sand	3165

Shows of oil	2895-97
	2922-29
	2979-96
	3165-69

Perforated 24/2922-29

" 12/2895-97
Acidized w/total 1500 gals.