

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
422 Union National Bldg. Wichita, Kansas

Company CITIES SERVICE OIL COMPANY
Farm Graham No. 6

SEC. 28 T. 14 R. 13W
S.E. SW NE
330' N & 990' E of W.4 Cor.

Total Depth. 3159' SLM
Comm. 1-25-48 Comp. 2-6-48
Shot or treated. Acidized
Contractor Holm Drlg. Co.
Cased. 5-8-48

County. Russell

KANSAS



CASING:
8-5/8" 280' Cem. W/175 Sx.
5-1/2" 3159' Cem. W/200 Sx.

Elevation. _____

Production. Pumped 254 B0, 24
BV, 24 hours.

Figures Indicate Bottom of Formations.

| | |
|----------------------|------|
| sand | 40 |
| shale | 55 |
| shale, shells & sand | 165 |
| iron & sand | 190 |
| sand & iron shells | 280 |
| shale & shells | 290 |
| shale, sand & shells | 440 |
| shale red | 690 |
| anhydrite | 725 |
| shale & shells | 1070 |
| salt, shale & shells | 1190 |
| salt & shale | 1360 |
| shale & gypsum | 1450 |
| shale & lime | 1555 |
| shale & shells | 1655 |
| lime & shale | 1985 |
| shale & shells | 2370 |
| lime | 2430 |
| shale & shells | 2525 |
| lime | 2840 |
| lime & shale | 2930 |
| lime | 2960 |
| lime & shale | 2966 |
| lime | 3155 |

3155 RTD = 3159 SLM

Corr. Top Lansing 2874
Corr. Top Gorham 3158
Penetration 1

Drilled Cement to 3136 SLM

Perf. 62 shots 2963-2989
Perf. 23 shots 2914-2920
Perf. 44 shots 2890-2904
Perf. 20 shots 2873-2878

2-23-48 Az. 2000 gals. 2963-2989
2-23-48 Az. 2000 gals. 2890-2920
2-23-48 Az. 1000 gals. 2873-2878