

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - SHIELDS OIL PRODUCERS
Farm - Geo. Rogg No. 6

SEC. 28 T. 14 R. 13W
SE 1/4 SW

Total Depth. 2987
Comm. 10-21-49 Comp. 12-10-49
Shot or Treated. Acid 2000 Tarkio Acid 5000 K.C.
Contractor.
Issued. 1-14-50

County. Russell
KANSAS



CASING:
20" 24' com. 7" 2325' com. w/100 sx.
12 1/2" 373' P. 5 1/2" 2905' com. w/50 sx.
10" 682' P.
8 1/4" 2262' P.

Elevation. _____

Production. Est. 10 bbls.

Figures Indicate Bottom of Formations.

cellar	10	shale blue	2350
sand	35	lime	2354
slate	80	shale	2380
sand HFI	105	lime	2405
slate	115	slate	2410
sand	145	lime	2425
iron	157	shale	2460
slate	160	lime	2440
iron	173	shale	2445
slate	240	lime	2505
sand	255	slate	2515
slate blue	373	lime brkn	2550
red rock	674	lime	2565
anhyd. lime	710	lime brkn	2570
red rock	805	lime Topoka	2722
slate blue	810	slate	2728
red rock	875	lime	2765
slate blue	920	slate	2775
red rock	980	lime	2821
slate blue	995	shale	2840
red rock	1000	Dodge lime	2855
slate blue	1085	red rock	2870
salt	1350	shale blue	2888
slate blue	1370	Lansing	2893
lime	1380	shale	2898
slate	1385	K. C. lime hrd	2927
lime brkn	1405	lime sft brn	2933
lime	1475	lime hrd	2960
red rock	1480	shale	2962
lime	1515	lime hrd	2982
lime brkn	1585	lime sft pay q	2987
red rock	1605	Total Depth	
lime	1640		
slate	1645	Tops:	
lime	1745	Anhyd.	674
slate brn	1750	Tarkio	2273
lime brkn	1825	Topoka	2570
shale pk	1830	Dodge	2840
lime	1875	Lansing	2888
red rock	1880		
lime	1955	Notes:	
red rock	1960	Perf. Tarkio, 87 shots	
lime	2010	2272-84 Acid 2000 rec. 14 gal.. H2O and small show	
slate	2015	of oil. K.C. pay, 2927-33, 2982-86, Acidized	
lime brkn	2150	Open hole 2905-2987, 5000 gal., Est. 20 BOPD	
slate blk	2160		
lime brkn	2187		
shale blk	2195		
lime	2214		
red rock	2219		
lime	2225		
red rock	2250		
lime	2255		
slate	2240		
lime brkn	2265		
slate brkn	2265		
slate blue 30	2275		
Tarkio Oil Pay	2282		
slate sdv	2310		
lime	2330		