


CS 1/2-NE-SE

SKELLY OIL CO.
C. Colliver No. 8.

SEC: 28 T. 14 R. 13W
CS 1/2, NE SE
990' fr NL 660' fr WL SE 1/4

Total Depth. 2890'
Comm. 11-19-40 Comp. 12-9-40
Shot or Treated. 12-9-40 6500 Gals. 2872-90
Contractor. Claude Wentworth Co.
Issued. 1-11-41 Rotary O-2874
Cable 2874-90

County. Russell



CASING:
10 3/4" 284'
6 " 2872'

Elevation.

Production. Pot. 1666 B.

Figures Indicate Bottom of Formations.

surface soil & shale	140	Tops: Ft. Dodge lime	2797
pyrites of iron	165	Lansing Lime	2843 SLM
shale & lime shells	300		
shale & shells	465	slight porosity & stained	
red bed & shale	650		2846-2850
anhydrite	680	pay formation	2873-2890
shale & red bed	890		
shale & shells	1125		
salt	1210		
salt & shale	1250		
shale & shells	1515		
anhydrite	1540		
shale	1560		
shale & shells	1725		
lime	1830		
shale & lime	1930		
lime brkn	2010		
shale & lime	2080		
shale & shells	2165		
shale	2200		
shale & shells	2300		
shale	2352		
shale & shells	2567		
lime	2594		
lime brkn	2610		
lime	2700		
lime brkn	2753		
lime	2830		
shale gy silty	2846		
lime gy oolitic & cryst	2850		
lime gy cryst, no porosity or sat.	2858		
lime gy cryst w/strks of shale	2876		
lime brown sft oolitic, porous & saturated	2877		
SLM 2877 equals	2874		
lime sft gy oolitic, porous & saturated	2876		
show of free oil	2876		
lime sft brown oolitic, porous & saturated	2880		
lime med hrd gy cryst w/little brown oolitic			
lime, porous & sat.	2884		
lime gy cryst & shaley w/little brown oolitic			
lime	2889		
Cored w/cable tools: 2889-90 rec. 1'			
all med hrd, gy cryst lime- spotted porosity & stained			
300' OIH in 2 hrs; 800' OIH in 6 hrs & 1200' OIH 12 Hr.			
Total Depth	2890		

Before acid 1200' OIH in
12 hrs.
After acid POB 8 hrs 555.36
bbls oil.