


BRADEN-MCCLURE DRIG.CO.
 Opdycke No. 1.

SEC.29 T.14 R. 13 W
 CNL NE NW

Total Depth. 2942'
 Comm. 10-30-41 Comp. 12-10-41
 Shot or Treated.
 Contractor. Braden-McClure Drlg.Co.
 Issued. 1-31-42

County. Russell



CASING:

15" 59'
 12" 390'
 10" 712'
 8" 2330'
 7" 2921'

Elevation.

Production. Pot. 364 B.

Figures Indicate Bottom of Formations.

cellar	10	shale blue	2085
clay sdy yellow	35	lime	2130
clay sdy	45	shale blue	2205
sand	65	shale	2222
shale blue	80	lime	2232
red rock	90	shale	2238
shale blue	165	red rock	2242
sand	200	lime shells & shale	2255
red rock	210	shale & shells	2280
shale blue	310	sh oil 2285	
iron	314	lime sdy	2290
shale blue	390	shale	2305
red rock	698	shale blue	2330
anhydrite lime	703	lime (sh oil 2335)	2350
lime	736	shale blue	2370
shale blue	739	lime	2375
red rock	900	shale blue	2385
shale blue	960	shale	2396
red rock	1010	lime brkn	2419
shale blue	1090	lime	2430
lime shell	1095	shale	2435
shale	1105	lime	2475
shale blue	1120	shale blue	2542
salt	1365	lime	2559
shale blue	1375	shale	2569
lime & shale	1430	lime	2595
shale & shells	1480	shale	2603
lime	1490	lime	2630
shale blue	1510	shale blue	2635
red rock	1515	lime	2662
shale blue	1521	shale	2667
lime	1545	lime	2710
shale	1550	shale	2715
lime	1610	lime	2756
red rock	1635	shale	2762
lime	1650	lime	2842
lime sft	1675	shale	2845
shale blue	1680	lime	2847
lime sft	1720	shale	2858
lime	1775	lime	2872
red rock	1780	red rock	2874
lime	1805	shale	2895
shale wh	1815	shale blue (K C 2899)	2913
lime	1830	lime	2909
shale blue	1835	shale	2912
shale & shells	1859	lime (sh oil 2925-30)	2940
lime	1873	oil pay - lime	2942
red rock	1881	Total Depth.	
lime	1900		
red rock	1908		
lime	1925		
shale	1940		
lime	1965		
shale wh	1970		
red rock	1986		
lime	2045		
red rock	2060		
lime	2075		