


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CITIES SERVICE OIL CO.
Carter No. 4.

SEC. 29 T. 14 R. 13W
CNL SE NE
990' N 660' W E $\frac{1}{4}$ Cor.

Total Depth. 3168=3166 SIM
Comm. 10-18-40 Comp. 10-29-40
Shot or Treated.
Contractor. Hisson & Wolfe Drlg. Co.
Issued. 12-7-40

County. Russell



CASING:
8 5/8" 297' Cem.
5 1/2" 3166' Cem.

Elevation.

Production. Pot. 1438 B.
Figures Indicate Bottom of Formations. Depth., No wtr

surface hole	184
iron	205
shale & iron	297
iron & sand	390
shale & red bed	700
anhydrite	738
shale & shells	1132
salt, shale, shells	1390
shale & lime	1673
lime brkn & chert	1744
lime brkn	1850
shale & lime	2652
lime	2898
chert & lime	2927
lime	3168

3168 Rot. T.D. = 3166 SIM

Total Depth.

1000 & 7000 Gals. 11-3-40

Corr. Tops: Lansing 2887
Gorham Sand 3165

Perforated Lansing-K.C., by
Lane-Wells, as follows:

11 shots 2920-31

24 shots 3074-82

34 shots 2981-93

36 shots 2922-33

12 shots 2904-08

Fillup: 200' oil in 25 min.
360' oil in 1 hr, 10 min.
500' oil in 2 hrs, 25 min.
800' oil in 4 hrs, 25 min.