


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.  
Farm- Edith Hickey No. 6

SEC. 30 T. 14 R. 13W  
NE NW NW  
330' fr NL 990' fr WL

Total Depth. 2260½  
Comm. 3-24-52 Comp. 4-16-52  
Shot or Treated.  
Contractor. Claude Wentworth Drlg. Co.  
Issued. 6-21-52

County Russell  
KANSAS



CASING:

10 3/4" 195' cem. w/275 sx  
7" 2248' cem. w/1050 sx

Elevation. 1721 DE

Production. 55 BO 5 BW

Figures Indicate Bottom of Formations.

surface soil & clay	35
sand	45
chalk	100
shale & shells	200
reamed 9 5/8" hole to	
13-3/4"	
shale & shells	420
red bed	705
anhydrite	735
shale & shells	1355
lime brkn & shale	1415
lime	1695
lime & shale	1750
lime	1840
lime & shale	2243
fine grained, shaley	
micaceous sand	2248
fine grained sand	2252
gry & brown fine grained	
micaceous sand with	
sandy shale	2256
same	2259
fine grained, gry	
sand	2260½
Total Depth	

Tops:  
Indian Cave Sand 2243

No shows 2243-2248'  
Slight show oil & odor in  
samples 2248-2252'  
Very slight show of oil  
2252-2256'  
No inc. in fluid 2256-59'  
No show, no inc. in fluid 2259-60½'  
Shot between 2247-2260½'  
Producing Formation:  
Indian Cave Sand 2247-2260½'