


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SKELLY OIL CO.
C.M. Phinney No. 1.

SEC. 30 T.14 R.13W
CN $\frac{1}{2}$ NE NW
330' fr NL 660' fr EL E $\frac{1}{2}$ NW $\frac{1}{4}$

Total Depth. 2040'
Comm. 4-21-40 Comp. 5-1-40
Shot or Treated.
Contractor. Claude Drlg. Co.
Issued. 6-22-40 Rotary 2040

County. Russell



CASING:
10 $\frac{3}{4}$ " 310'

Elevation.

Production. Dry, Abnd hole

Figures Indicate Bottom of Formations.

sand & shale	100
shale & shells	312
shale	345
shale & red bed	652
anhydrite & pyrites	700
shale & shells	1055
shale & salt	1260
shale & shells	1412
shale & lime	1474
lime	1539
shale & lime	1578
lime	1664
shale & lime	1702
lime	1860
shale & lime	2040
Total Depth.	

Stopped drilling on May 1, 1940
After drilling to a total
depth of 2040' knocked off btm
three joints of 10 $\frac{3}{4}$ " csg.
Drove same to btm & after
milling on casing for 48 hrs,
were unable to mill up, side
track, or straighten whereby
drilling ahead could be
continued.
It was therefore decided to
plug and abnd the hole & skid
rig to new location