

31-14-13W

TYPE

*** AFFIDAVIT OF COMPLETION FORM**

ACO-1 WELL HISTORY
Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F _____ Letter requesting confidentiality attached.

C _____ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run X.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5184 EXPIRATION DATE 6-30-84

OPERATOR Shields Oil Producers, Inc. API NO. 15-167-22,351

ADDRESS Shields Bldg. COUNTY Russell

Russell, Kansas 67665 FIELD Hall-Gurney

** CONTACT PERSON M. L. Ratts PROD. FORMATION Kansas City
PHONE 913-483-3141 _____ Indicate if new pay.

PURCHASER Citco Petroleum LEASE Miller "A"

ADDRESS _____ WELL NO. 6

Tulsa, Okla. 74102 WELL LOCATION W/2 SW SE

DRILLING Shields Drlg., Co., Inc. #5655 330 Ft. from West Line and

CONTRACTOR ADDRESS Shields Bldg. 660 Ft. from South Line of (82)

Russell, Kansas 67665 these (Qtr.) SEC 31 TWP 14 RGE 13 (W).

PLUGGING CONTRACTOR ADDRESS _____

WELL PLAT (Office Use Only)

		31	
		X	

KCC
KGS
SWD/REP _____
PLG. _____
NGPA _____

TOTAL DEPTH 2890 PBTD _____

SPUD DATE 4-6-84 DATE COMPLETED 4-17-84

ELEV: GR 1691 DF 1693 KB 1696

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE 62,832-C.

Amount of surface pipe set and cemented 666 DV Tool Used? No.

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil), Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

M. L. Ratts, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.

WEL-41-18

502151

ACO-1 Well History

Side TWO

OPERATOR Shields Oil Producers, Inc. LEASE NAME Miller "A" SEC 31 TWP 14 RGE 13 (W)

WELL NO 6

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<p>Check if no Drill Stem Tests Run.</p> <p>Check if samples sent Geological Survey.</p> <p>D.S.T. #1 2805-2842 Times: 30-45-30-45 Rec. 30' Mud</p> <p>I.F.P. - 51# to 51#</p> <p>I.S.I.P. - 102#</p> <p>F.F.P. - 51# to 51#</p> <p>F.S.I.P. - 102#</p>			<p>Anhydrite</p> <p>Heebner Sh</p> <p>Toronto Lm</p> <p>Douglas Sh</p> <p>L-KC Lm</p>	<p>666</p> <p>2775</p> <p>2792</p> <p>2806</p> <p>2842</p>

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
5,500 gal 15%	2872-2890

Date of first production 4-25-84	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity
Estimated Production-I.P.	Oil 25 bbls. Gas Show MCF Water 20 % 5 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Used at well	Perforations Open hole	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4	8 5/8	24	666	Quickset	350	
Production	7 7/8	5 1/2	14	2872	Common	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			None		
Size	Setting depth	Pecker set at			