


THE TEXAS CO.
N. Schnoor No. 3.PLUGGING BACK RECORD.Plotted Texas Co. 31 T. 14 R. 13W
NE NW SW
330' fr N 990' fr WL SW $\frac{1}{4}$ Total Depth. 3216 P.B.3082
Comm. 2-21-38 Comp. 4-23-38
Shot or Treated. No
Contractor. J.J.Hall
Issued. 5-30-42

County. Russell



CASING:

Cable

15 $\frac{1}{2}$ "	22'
12 $\frac{1}{2}$ "	330'
10 "	695'
8 $\frac{1}{2}$ "	2400'
7 "	2944'
53/16"	3208'

Elevation.

Production. Pot. 370 B.

Figures Indicate Bottom of Formations.

cellar	10	lime shells	2025	lime	3206
shale	13	lime	2030	shale	3208
sand	23	shale blue	2035	lime	3211
shale blue	35	shale	2045	sand	3216
red rock	45	lime	2075	Total Depth.	
sand	120	shale blue	2090		
iron	125	lime 2 $\frac{1}{2}$ BW 2055-65	2120		
shale	130	shale blue drk	2130		
shy shale	145	shale	2145		
shale	170	lime	2160		
sand	199	shale	2245		
shale blue	270	lime shell	2250		
shale drk	295	shale brown	2270		
shale blue	320	lime	2272		
shale	330	shale brown	2280		
shale blue	335	shy lime	2285		
red rock HFW 365-75	365	shale drk	2315		
sand red	375	sh oil & gas 2280-2285			
red rock	689	shale	2340		
lime	719	lime	2355		
shale blue	725	shale blue	2380		
red rock	885	shale	2405		
shale blue	925	lime	2425		
red rock	995	shale	2435		
shale blue	1030	lime	2445		
shale	1095	shale blue	2450		
salt	1375	lime	2465		
shale	1381	shale blue	2470		
shale blue	1425	lime	2490		
shale white	1430	shale	2515		
lime	1465	shale blue	2545		
shale	1480	lime	2565		
lime	1500	shale blue	2570		
shale brown	1525	lime	2590		
lime	1540	shale	2605		
shale blue	1545	lime	2720		
lime	1605	shale	2725		
shale brown	1625	lime	2848		
brkn lime	1650	shale blk break	2852		
lime	1680	lime	2855		
shale blue	1690	shale blue	2865		
lime	1720	lime Dodge	2880		
shale	1730	shale	2915		
lime	1740	sh oil at 2873			
lime sharp	1760	lime	2931		
shale brown	1775	shale	2940		
lime	1804	lime $\frac{1}{2}$ BOH 2976-81	3027		
shale	1809	pay	3035		
lime	1833	lime hrd	3040		
shale blue	1850	lime	3073		
lime	1875	shale green	3075		
shale	1880	lime	3083		
lime	1905	shale blk	3085		
brkn lime	1935	lime	3146		
lime	1965	shale	3180		
red rock	1980	lime	3189		
lime	2010	shale	3191		

PLUGGING BACK RECORD.Comm. 7-27-41
Comp. 10- 1-41
Old T.P. 3216.
Prod. Pot. 25 B.O. 25BW
Plugged back with cement
sand and calseal from
3216-3082Perf. 5 $\frac{1}{2}$ casing 3050
Ripped pipe 3057 and
pulled 3057 of 5 $\frac{1}{2}$ " Cas.
Tested well and got
25 bbls oil and 25 BW