

15-167-20958
21-14-13W

State Geological Survey
WICHITA BRANCH

DRILLERS' WELL LOG

DATE COMMENCED: October 31, 1976
DATE COMPLETED: November 4, 1976

Well Operations
"SHERWOOD # 9"
NW SE NW
Sec 21-T14-R13W
Russell County, Kansas

ELEVATION: 1811 K.B.

FORMATION DATA

0 - 16' Surface Soil, Shale and Post Rock
16 - 47' Post Rock
47 - 247' Clay and Sand Streaks
247 - 743' Shale, Red Bed, Sand Streaks
743 - 784' Anhydrite
784 - 1440' Shale, Red Bed
1440 - 1625' Shale, Lime Streaks
1625 - 2227' Lime, Shale
2227 - 2360' Lime, Shale, Sand Streaks
2360 - 2480' Shale and Lime
2480' RTD

Anhydrite 743
RTD 2480

SURFACE PIPE: Set used 28#
3 5/8" at 247' w/150 sacks
Common cement, 2% Gel, 3% CC.

PRODUCTION PIPE:
Ran new 14#, 5 1/2" casing at 2479'
w/100 sacks 50/50 Pozmix, w/18%
salt .75% CFR2 and 1/4# Flo seal
per sack.

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 9th day of November, 1976.

Clorinda M. Hague
Notary Public



Mr. [redacted] Address: April 11, 1978