


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- COOPERATIVE REFINERY ASSOCIATION, INC.
 Farm- Jones "A" No. 5

SEC. 22 T. 14 R. 13W
 C NE NW

Total Depth. 3224'
 Comm. 2-2-65 Comp. 2-12-65
 Shot or Treated.
 Contractor. Harms Drlg
 Issued. 7-31-65

County Russell
 KANSAS



Elevation. 1746' K.B.

Production. Pmp. 54 BO & 26 BWPD

CASING:

8 5/8" 425' w/300 sx cem.
 5 1/2 3224' w/325 sx cem.

Figures Indicate Bottom of Formations.

??	0-390
red bed	683
Anhydrite	715
red bed	800
red bed, shells, shale	1379
lime, shale	2093
shale, lime stks	2238
lime	2267
shale	2309
lime	2360
shale, lime	2600
lime	2817
shale	2822
lime	2850
shale	2883
lime	3028
chert	3065
lime	3178
Arbuckle	3224
Total Depth	

TOPS: SCOUT	
Fort Riley	1655
Tarkio sand	2252
Tarkio lime	2311
Elmont	2378
Topeka	2584
Heebner	2816
Toronto	2834
Lansing Kansas City	2881
B/Kansas City	3155
Arbuckle	3168
Arbuckle "Por"	3176

Ran electric log.