

DRILLERS' WELL LOG

DATE COMMENCED: October 20, 1976  
DATE COMPLETED: October 24, 1976

Mai Operations  
"CAMPBELL # 17"  
NW SE SW  
Sec 22-T14-R13  
Russell County, Kansas

ELEVATION: 1757 K.B. (Est.)

0 - 196'	Surface soil, shale, sand streaks
196 - 696'	Hard sand, shale, shells, red bed
696 - 735'	Anhydrite
735 - 1380'	Shale, red bed & shells
1380 - 2430'	Lime and Shale
2430'	RTD

FORMATION DATA

Anhydrite	696
RTD	2430

SURFACE PIPE:

Set used 28# 8 5/8" pipe at 237' w/150 sacks Common, 2% Gel, 3% cc.

PRODUCTION PIPE:

Ran used 14# 5 1/2" pipe at 2429' w/100 sacks 50/50 Pozmix, w/18% salt & .75% CFR2 w/1/4# Floseal persack.

AFFIDAVIT

STATE OF KANSAS }  
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 26th day of October, 1976.

Dorothy M. Hague   
Notary Public



Commission Expires: April 11, 1978