

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **SHIELDS OIL PRODUCERS, INC.**

SEC. 20 T. 14 N. 13W
 LOC. SW NE NE

FARM **Rogg "C"** NO. 9

TOTAL DEPTH **3300**
 COMM. **1-23-67** COMP. **1-30-67**
 SHOT OR TREATED
 CONTRACTOR **Shields Oil**
 ISSUED **3-18-67**

COUNTY **Russell**
 KANSAS



CASING

20	10	
15	8	5/8" @ 258' w/175 sx
12	6	
13	5	

ELEVATION **1861'KB**

PRODUCTION **DRY/ARB**

..... Figures Indicate Bottom of Formations

Post rock & shale	150'	TOPS: SAMPLE	
Shale & sand	260'		
Shale, shells & pyrite	385'	Heebner	2944
Hard sand	410'	Lansing	3018
Shale, shells & redbed	710'	Arbutkle	3293
Redbed	804'		
Anhydrite	844'		
Shale, shells & salt	1,325'		
Shale & shells	1,500'		
Lime & shale	1,800'		
Lime	2,000'		
Lime & shale	2,725'		
Lime	3,300'	R T D	

NOTES

- DST #1 3,278'-3,295' Tool open 1 hr. w/ fair blow decreasing to weak. Recovered 60' SO & GCM, 60' SOCWM, 5' water. IBHP-880#, IFP-0#, FFP-0#, FBHP-615#/20min.
- DST #2 3,278'-3,300' Tool open 1 hr w/ weak blow thruout. Recovered 60' mud w/ scum of oil, 40' muddy water. IBHP-820#, IFP-0#, FFP-0#, FBHP-615#/20min.