


15-167-21239

State Geological Survey

KANSAS DRILLERS LOG WICHITA BRANCH

S. 25 T. 14S R. 13 W
 Loc. 1650' FSL-990' FWL
 County Russell

API No. 15 — 167 — 21239
 County Number
 Operator Cities Service Co.
 Address 209 E William, 700 Sutton Place, Wichita, Ks 67202
 Well No. 10 Lease Name Weimester "A"
 Footage Location 1650 feet from (N) (S) line 990 feet from (E) (W) line
 Principal Contractor Woodman-Ianitti Oil Co. Geologist on well site Sam Houston
 Spud Date 9-28-78 Total Depth 3185' P.B.T.D. _____
 Date Completed 11-13-78 Oil Purchaser Continental Oil Co.



Elev.: Gr. 1697'
 DF 1699' KB 1702'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	631'	50-50-pozmix	450	2% CACL-2
Production	7 7/8"	5 1/2"	14#	2998'	50-50 pozmix	300	10% Salt+.75 CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
---	---	---	2	---	2193'-2298'

TUBING RECORD

Size	Setting depth	Packer set at
2		---

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals. 15% MCA. Fractured with	
3000 gals. Pad, 9000 gals. 10-20 sand	2193' - 2298'
2500 gals. 2% KCL water	

INITIAL PRODUCTION

Date of first production 11-13-78 Producing method (flowing, pumping, gas lift, etc.) pumping
 RATE OF PRODUCTION PER 24 HOURS Oil 12 bbls. Gas MCF 80 bbls. Water 80 bbls. Gas-oil ratio CFPB
 Disposition of gas (vented, used on lease or sold) Producing interval(s) 2193' - 2298'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Cities Service Co.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

10

Lease Name

Weimeister "A"

oil

S 25 T 14 S 13 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
(see log attached)				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature *W. J. Devaney*

Region Operations Manager

Title

November 1978

Date