


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - W. S. Goodheart No. 10

SEC. 25 T. 14S R. 13W
Nw NE SE

Total Depth. 2908'
Comm. 10-17-48 Comp. 11-8-48
Shot or Treated. acidized
Contractor. Powell-Brunson Drig. Co.
Issued. 12-25-48

County. Russell
KANSAS



CASING:
10 3/4" 622' Cem. 1/500 Sx.
7" 2827 1/2' Cem. 1/100 Sx.

Elevation. 1673 Ind.

Production. 205 bbl no wtr

Figures Indicate Bottom of Formations.

sandy surface soil	103
redbed & shale	319
redbed & shells w/streaks of iron	439
redbed, iron & sand	612
anhydrite	640
redbed	910
blue shale	1000
shale, shells & salt	1275
lime & shale	1320
shale & broken lime	1455
lime	1805
lime & shale	1910
lime	1990
lime & shale	2175
shale	2350
broken lime	2430
lime & shale	2545
lime	2658
lime & broken shale	2718
lime	2758
lime & shale	2828
lime	2908

Total Depth

Tops: Tarkio	2170
Topoka	2497
Hebner	2733
Brown Lansing	2810
White Lansing	2826

11-7-48 swabbed hole down, swabbed
8 bbl oil per hr for 8 hr.
11-8-48 acidized w/ 3000 gal max.
pressure 725# minimum
" 400# pulled tubing
swabbed to bottom, swabbed
from bottom 23 bbl per hr
total of 276 bbl oil no wtr in 12 hr