


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY  
Farm- C. W. Shaffer No. 2

SEC. 18 T. 14 R. 13W  
SE SE NE

Total Depth. 2386 P.B. 2383  
Comm. 5-3-52 Comp. 6-1-52  
Shot or Treated.  
Contractor. Earl F. Wakefield  
Issued. 8-2- 52

County Russell  
KANSAS



CASING:  
10 3/4" 820 com. w/700 sx.  
7" 2380 com. w/105 sx.

Elevation. 1828 D.F.  
*1801 (2nd)*  
Production. Pmp. 80 bbls. & 5 wtr

Figures indicate Bottom of Formations.

clay yellow	20
shale blue	160
red rock	165
shale blue	200
red rock	305
shale lgt	325
shale blue	335
shale lgt	360
sand	385
shale	454
sand	470
red rock	805
red rock & gyp.	815
anhyd.	820
lime	830
red rock	1010
shale blue	1060
red rock	1105
shale blue	1225
salt	1470
lime	1475
shale blue	1478
lime	1490
shale blue	1497
lime	1520
shale lgt	1530
lime	1545
shale	1550
lime	1560
shells & shale	1585
red rock	1590
lime	1675
lime brkn	1690
red rock	1698
lime brkn	1720
lime	1823
lime sharp	1833
shale	1843
lime	1900
shale & shells	1926
lime	1970
shale	1980
lime	2055
red rock	2068
lime	2118
shale blue	2138
lime	2198
shale blue	2205
shale & shells	2228
lime	2240
shale blue	2243
lime	2271
shale blue	2278
lime	2332
shale	2345
lime	2350
Tarkio sand	2366
shale	2379
Tarkio sand	2386
Total Depth P.B. 2383	

Mea. from BH to DF 6', BH to GL 3.5

Tops:  
Upper Tarkio 2358  
Lower Tarkio 2379