

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE TEXAS COMPANY.
W.S. Goodhardt No. 1

SEC. 25 T. 14 R. 13W.
CW $\frac{1}{2}$ SW SE
630' f SL 330' f WL SE $\frac{1}{4}$

Total Depth. 3118 $\frac{1}{2}$
Comm. 5-9-41 Comp. 5-22-41
Shot or Treated.
Contractor. Holmerich and Payne, Inc.
Issued. 6-21-41

County Russell.



Casing. Rotary 3111
Cable 3118 $\frac{1}{2}$
103/4" 388' cemented.
7" 3111' cemented.

Elevation.

Production. Pot. 2045 B.

Figures Indicate Bottom of Formations. 7 $\frac{1}{2}$ % wtr, Dophograph.

surface loam	30
sand and shale	125
sand sholls shale pyrite	322
red bed, shale & shells	615
anhydrite & shale	642
red bed, shale & shells	815
shale & shells	1030
salt and shale	1250
shale and shells	1282
anhydrite and shale	1375
shale some anhydrite	1412
shale sholls limo and sand	1567
sdv lime and shale	1752
sdv lime	1762
brokon lime & sand	1886
Br. lime sand and pyrite	2006
brokon lime	2645
lime	2733
lime and shale	2821
lime	2843 small show oil 2836
lime soft	2848
lime	2965 good show oil 2843-49
lime and shale	3020
lime	3118 $\frac{1}{2}$
Total Depth.	

Top Arbuckle 3111'

Dumped 50 gal acid in hole to clean hole up.