

26-14-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LOUIS M. MAI
Farm- Shaffer "C" No. 5

SEC. 26 T. 14 R. 13W
SE NW NE

Total Depth. 3160'
Comm. 10-13-64 Comp. 10-23-64
Shot or Treated.
Contractor. Mast Drilling, Inc.
Issued. 1-30-65

County Russell
KANSAS



Elevation. 1722 K B

Production. 25 BOPD, NW

CASING:

8 5/8" surf. pipe 195' cem.
w/135 sx.

Figures Indicate Bottom of Formations.

top soil & sand	90
shale	196
shale, sand & red bed	445
red bed	652
Anhydrite	686
shale & shells	1175
shale	1350
lime & shale	1721
lime	1860
lime & shale	2148
shale, sand & lime	2350
shale & lime	2588
lime	2690
lime & shale	2865
lime	3059
shale & lime	3140
lime	3160
Total Depth	

TOPS -Sample	
Grand Haven	2208
1st Sand	2217
Dover Lime	2231
Langdon	2236
Tarkio	2278
Willard	2299
Topeka	2548
Heebner	2782
Toronto	2802
Kansas City	2851
Conglomerate	3151