

SKELLY OIL COMPANY  
C. Colliver No. 3.

SEC. 28 T. 14 R. 13W  
NW 1/4 SE 1/4 15-107-0248  
330' fr NL & EL SE 1/4

Total Depth. 2897'  
Comm. 5-14-39 Comp. 6-3-39  
Shot or Treated. 6000 Gals. 2874 1/2 - 97  
Contractor. Claude Drlg. Co.  
Issued. 7-22-39

County. Russell



CASING:  
10 3/4" 287'  
6 5/8" 2874 1/2'

Rotary 2876 1/2  
Cable 2897

Elevation.

Production. Pot. 1498 B.

Figures Indicate Bottom of Formations.

surface soil & clay	120
lime & iron	305
shale	310
sand	380
red rock	600
shale & shells	690
anhydrite	720
shale & shells	975
shale & lime	1060
shale	1095
salt	1250
shale & lime	1305
brkn lime	1400
shale & lime	1533
brkn lime	1592
lime & shale	1667
brkn lime	1710
lime & shale	2270
shale	2300
lime & shale	2525
brkn lime	2584
limo	2845
dk gy sand & shale sft	2855
dense gy shale w/little	
cherty limo	2858
dense gy silty shale	2863
limo gy cryst.	2865
no porosity or saturation	
limo hd gy cryst	2871
no porosity or saturation	
mod hrd gy limo	2878
no porosity or saturation	
limo gy & brown oolitic	2880
porous w/slight oil stain	
SL Corr Rotary table to	
derrick floor 2880-2876 1/2	
limo gy & brown cryst	2880
porous & stained, slight	
sh oil	
limo gy & brown oolitic	2882
Cored w/CT 2882-85 roc 3'	
top 2' hrd gy cherty limo	
no porosity or sat.	
btm 1' mod hrd gy cryst	
limo. no por or sat.	
Cored w/CT 2885-88 roc 3'	
top 1' hrd gy cryst limo	
no por or sat.	
btm 2' drk gy cryst limo	
no por or sat.	
Cored w/CT 2888-90 roc 2'	
all drk gy hd cryst limo	
no por or sat.	
Cored w/CT 2890-94 roc 4'	
top 1' hrd gy cryst limo	
no porosity or sat.	
2' gy & brwn oolitic limo	
porous & stained	
btm 1' very sft gy & brwn	
oolitic limo, porous &	
stained, 50' OIH	

Cored w/CT 2894-97 roc 3'  
top 2 1/2' gy limo & dk shale  
no porosity or saturation  
btm 6" brwn por. oolitic  
limo, saturated  
Hole filled 150' w/oil in  
1 hr; 300' in 2 hrs; 450'  
in 3 hrs; and 600' in 6  
hrs. Showed no wtr.  
Total Depth 2897

Production before acid  
600' OIH 6 hrs  
Production after acid  
499.25 (Pumped in 8-hr  
test) Established 24-hr  
calc. potential of 1498 B.

Top Lansing limo 2858 1/2 SIM  
Main body pay formation  
2874 1/2 - 2897