

27-14-13W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SHIELDS OIL PRODUCERS, INC.
Farm- Rein No. 1

SEC. 27 T. 14 R. 13W
SW NW NW

Total Depth. 3204'
Comm. 6-3-64 Comp. 6-9-64
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 10-17-64

County Russell
KANSAS



CASING:
8 5/8" 260' cem w/200 sx.
4 1/2" 2406' cem w/75 sx.

Elevation. 1751' RB

Production. Dry

Figures Indicate Bottom of Formations.

clay, sand & shale	201
hard sand & pyrite	210
shale	260
shale, shells & redbed	700
Anhydrite	740
shale & shells	1400
shale & lime strks.	1520
lime & shale	1635
lime	1935
lime & shale	2615
lime	3204 .TD
Total Depth	

TOPS: LOG

Anhydrite (sample)	700
1st. Tarkio Sand	2270
Heebner	2828
Toronto	2846
Lansing-Kansas City	2892
Conglomerate Shale	3178
Reagan Sand	3199

DST #1 2896-2942' Tool Op. 1 hr. w/good
blow throughout. Rec. 300' gas, 480' gassy
mud, 90 wtry mud, IBHP 912#, IFP 67#, FFP
245#, FBHP 901#/20 mins.

DST #2 3172-3204' Tool Op 1 hr. Rec.
1380' wtr. IBHP 956#, IFP 111#, FFP 623#,
FBHP 812#/20 mins.