

28-14-13W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Skelly Oil Co.
Farm- Colliver No. 18

SEC. 28 T. 14 R. 13W
-- CE/2 SW SE

1320' FEL 40' FSL SE/4 1000'
County RUSSELL 32 FSL 1411 FEL
KANSAS

Total Depth. 3000
Comm. 4- 2-64 Comp. 5-7-64
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 11-7-64



Elevation. 1718 GR

Production. Water Injection Well

Figures Indicate Bottom of Formations.

Shale and sand	140
Iron pyrite	248
Hard sand, shale	315
Shale, shells, ...	585
Shale and shells	644
Anhydrite	654
Anhydrite	680
Shale, salt and shells	1075
Shale w/lime strks	1475
Lime and shale	2610
Lime	2805
Lime and shale	2900
Lime	3000
TOTAL DEPTH	

SAMPLE TOPS

Anhydrite	644
Tarkio	2274
Topeka	2546
Toronto	2797
Lansing Kansas City	2850

TREATMENT #1 2872-2894

Treated through casing by Halliburton
w/ 3000 gall. CRA 15% acid.
2872'-2874 - 2' - 6 shots
2877 - 2879 - 2' - 6 shots
2883 - 2898 - 15' 45 shots

TREATMENT # 2 - Acid- 2873'-2898'

Treated through 5 1/2" casing w/ 6000
Gal. CRA 15% Acid & 1000# Rock salt