

29-14-13W

Geol. 63 6M 6-10 R

AUG 16 1969

WELL RECORD

Company Cities Service Oil Co. Well No. 8-W Farm Carter "A"
 Location 1520' FNL & 1320' FEL Sec. 29 T. 14 R. 13W
 Elevation 1756 KB County Russell State Kansas
 Initial Prod. Drilled for L-KC Injection Well. Contractor Peel Brothers, Inc.
 Acid 2250 gallons Drlg. Comm. April 13, 1969
 T.D. 3025' Drlg. Comp. May 30, 1969

CASING RECORD:

8-5/8" set @ 291' with 175 sx
 4-1/2" set @ 3024' with 300 sx
 DV-tool @ 720' with 200 sx

FORMATION RECORD:

surface & shale	0-138'
sand & shale	295
shale	396
red bed & shale	694
Anhydrite	1120
shale & lime	2615
lime	3025 TD

DRILL STEM TESTS:

None

ELECTRIC LOG TOPS:

Heebner	2820' (-1064)
Toronto	2840' (-1084)
Lansing-Kans. City	2880' (-1124)

COMPLETION:

Perf. 2927-32', "D" zone.
 Acidized with 2250 gals., 2 stages.

SLOPE TESTS:

785', 1/2°
 1403', 1°
 1860', 2°
 2300', 1 1/2°
 2800', 1°
 3020', 1 1/2°

