


29-14-13W
Plotted Texas CO. !CITIES SERVICE OIL CO.
Opdycke No. 1.

SEC. 29 T. 14 R. 13W

CSL NE NW

990'S 660'W of N $\frac{1}{4}$ Cor.
4620 FSL; 3300 FEL - 1000

County. Russell



Total Depth. 3252'
 Comm. 4-10-41 Comp. 4-27-41
 Shot or Treated. None
 Contractor. Corbett-Barbour Drlg. Co.
 Issued. 5-24-41

CASING:

10 $\frac{3}{4}$ " 332' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil, sand, shale & iron	196
lime & iron w/strks shale	300
sd lime & iron	333
shale & sand shells	400
red bed	695
anhydrite	735
red bed	1050
shale & lime shells	1175
salt	1240
shale & lime	1420
lime	1980
shale & lime	2188
lime brkn	2267
shale & shells	2345
shale & lime	2393
lime brkn	2415
lime	2439
shale & shells	2546
shale	2555
lime	2590
shale & lime	2618
shale	2628
lime	2655
shale & lime	2789
lime w/strk of shale	2841
lime	2866
shale & lime	2899
lime	2941
lime cored (rec. 7')	2948
lime	3142
shale & lime	3156
lime	3177
cored sand (rec. 6')	3184
shale	3194
shale & shells	3217
sand	3219
sand & granite	3252
Total Depth.	

Tops: Lansing	2899
Gorham Sand	3173
Reagan	3216
Granite Wash	3219
Penetration	33