

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Plotted Texas CO

DEEPENING RECORD:

Company - SINCLAIR PRAIRIE OIL CO.
Farm - Geo. M. Rogg No. 6

SEC. 29 T. 14 R. 13W
CNL SE SE
660' E & 990' SL SE $\frac{1}{4}$

Total Depth. 3263'

Comm. 7-25-39

Comp. 8-6-39


Shot or Treated. Acid. 2000 gals., 6000 gals. 89 shots 2902-12

Contractor. Harbar Drlg. Co.

Issued. 4-2-49

County. Russell

KANSAS



CASING:
10-3/4" 145' 7" 3145'

Elevation. 1737

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	130
shale & sand	145
sand & iron	290
shale & iron	370
red bed	530
shale & shells	675
anhydrite	710
shale & shells	865
shale & lime shells	1095
salt	1325
shale & shells	1345
shale & lime shells	1490
lime	1522
shale	1537
lime brkn	1587
lime	1600
shale & lime	1650
lime	1695
lime & shale	1785
lime	1865
lime & shale	2084
shale & shells	2195
shale	2340
shale & lime	2402
shale	2410
lime	2420
shale & shells	2495
lime & shale	2618
lime hrd	2656
shale	2660
lime & shale	2720
lime	2835
lime & shale	2860
shale	2870
lime	2906
sand	2910
lime	2953
lime sft	2983
lime	3107
lime & shale	3147
sand	3148
Total Depth - Derrick Floor	

and drilled on to Gorham, found shoe at 3145 & cleaned out to 3142 old T.D. for show oil & 100' sulphur wtr. in 15 mins. filled up 1000' wtr in 10 hrs. 5 BO on top of wtr.

DEEPENING RECORD:

Deepened by Sinclair Prairie
Total Depth 3263'
Comm. - 7-31-47
Comp. - 8-5-47
Prod. - S.W.D.W.

gorham sand	3263
sand hrd	3263
Total Depth	

Top Gorham Sand 3145

Cored 2860-77 full red. 2860-70

shale 2870-77 lime show oil

Top K.C. lime 2868 (rig floor)

pay 2904-14 in oolitic zone.

Acid, W/2000 gals. acid. Pmp.

out load & then pmped 6 bbls.

fluid an hr. about 1 BO, acid.

W/6000 gals. acid. & after rec.

oil used in acid. well pmped 19

hrs. making 102 BW & 6 BO, after

3 days pmping & testing. well made

8.64 BO & 42 BW in 24 hrs. ending

8 A.M. August 17th. Then run cement

squeeze job on perforations in K.C.