

December, 1942

Stanolind, # 1 Missmer
C E $\frac{1}{2}$ SE NE, 22-14s-13w
Elev. 1777'

Cable tools

Pennsylvanian Conglomerate 3222'-3224'

3222-3224 Sandy limestone. Basal two or three feet of buff to red limestone includes scattered sand grains and rare stained chert fragments.

Arbuckle Top 3224' Penetration 47' Subsea -1447'

Post Boyce 3224'-3250'

3224-3250 Dolomite, white, coarsely crystalline.

Boyce 3250'-3271' TD

3250-3255 Sandy dolomite, white, medium to coarse. Chert, quartzose, sandy, with poor white solid oolites.

3255-3265 Dolomitic sand to very sandy dolomite. About 55% sand in residue, grains coarse, faceted.

3265-3271 Finely ground sand and dolomite. Test made 2500 feet of water in 4 hours at TD

Remarks: Test dry and abandoned in July, 1941.

RFW