

Texas, # 3 Goodhart
NW SE SE, 25-14s-13w
Elev. 1680'

Rotary to 3113' equals 3111' corr.

Pennsylvanian conglomerate

A foot or so of conglomerate as indicated by a few
worn fragments of Cotter chert in rotary samples.

Arbuckle	Top 3104'	Penetration 9'	Subsea -1424'
	3104-3111	Dolomite, white, coarsely crystalline, slightly sandy, oilstained. <u>Post Boyce</u> .	
	3111-3113	Very sandy dolomite to dolomitic sand. About 50% sand in residues, medium and coarse. Some red grains. Some very coarse sand (plus 1 mm). Three samples. <u>Boyce</u> .	

Remarks: Test made 1207 bbl. well.

RFW