


SKELLY OIL CO.  
C. Colliver No. 5

SEC. 28 T. 14 R. 13W.  
CS  $\frac{1}{2}$  NE SW  
660' fr EL 990' fr NL SW  $\frac{1}{4}$

Total Depth. 2912  
Comm. 10-6-39 Comp. 11-10-39  
Shot or Treated. yes  
Contractor. Claude Drlg. Co.  
Issued. 2-10-40

County - Russell.



	Rotary	2895 $\frac{1}{2}$
CASING.	Cable	2912
103 $\frac{1}{4}$ "	301'	
7"	2894'	

Elevation.

Production Pot. 1482 B.

Figures Indicate Bottom of Formations.

surface soil sand and shells	163		
pyrites of iron	168	11-11-39	5000 gal acid. 2906-2912
pyrites of iron and lime	190	11-11-39	3000 gal acid 2894-2898
shale and pyrites of iron	222		
shale and shells	314		
shale and shells	375		
red beds and shells	600		Top Lansing line 2875
shale and shells	1120		Main body pay formation 2895 $\frac{1}{2}$ -2912
salt	1325		
shale and shells	1485		
lime	1520		
broken lime	1682		
shale	1702		
lime	1879		
shale	1896		
lime	1919		
lime and shale	1953		
shale and shells	2028		
shale	2075		
shale and shells	2208		
shale	2295		
shale and shells	2370		
shale and pyrites of iron	2374		
shale	2392		
shale and lime	2473		
shale	2461		
shale and lime	2556		
lime	2823		
lime and shale	2861		
grey chalky lime and shale	2872		
grey crystalline lime	2875		No porosity or sat.
S.L corr.	2875 equals 2878		
Dense grey crystalline lime with streaks of shale	2895		
brown oolitic lime	2896 $\frac{1}{2}$		
porous with slight sat.			
Corr. 2896 $\frac{1}{2}$ SLM rotary table equals			
2895 $\frac{1}{2}$ SLM derrick floor			Good show oil on cleaning out to bottom.
hole filled 100' oil in 1 hour.			
150 with oil in 2 hours.			
200' oil in 3 hours.			

DRILLED

grey crystalline oolitic lime 2897  
porous and stained no increase in fill up of oil  
CURED with cable tools. 2897 to 2900 Rec 3'  
All grey crystalline lime slight porosity and stained hard  
2900 to 2901 Rec 1'  
all grey shaley lime no porosity or sat.  
2901 to 2904 Rec 3'  
All grey crystalline lime with shaley streaks no porosity or sat.  
400' oil in hole in 6 hours.  
500' oil in hole in 12 hours.  
Drilled.  
grey and brown oolitic lime  
soft 10% shale 2908 porous  
brown porous oolitic lime sft 2912 porous 1500' OIH in 14 hours.  
2000' OIH in 20 hours.

Total Depth.