

Gore #8 Boxberger
Russell Co., KS.

W/2 NW/4 NE/4 Sec. 26-14S-14W, Russell Co., KS.
Elevation: 1800 KB

CORE DESCRIPTION

Core#1.2964-2990 Full recovery

2964-65	SH. GRN. GRY.
2965-70	LS. FOSIL. F. VUG. & FR. POROSITY BU. O. CHERTY @ 70.
2970-79	LS. SHY.
2979-82	SH. DR. GRY. CALC.
2982-84	LS. SHY.
2984-85	LS. PT. FOSIL. SCAT. VUG. POROSITY BU. O.
2985-90	LS. F. X. DSE.

Gore #8 Boxberger
Russell Co., Ks.
W/2 NW/4 NE/4 Sec. 26-14S-14W
ELEVATION: 1800 KB

CORE DESCRIPTION

Core #2 3106-3121 Full recovery

3106-07	SH. DR. GRY.
3107-09	LS. GRY. SH. LAM. DSE.
3109-10	SH. DR. GRY.
3110-14	LS. SH. LAM.
3114-19	LS. PT. FOSIL. OOL. P. SCAT. VUG. POROSITY BU. O. IN SPOTS (16-18 95% SATR.)
3119-21	LS. DSE.

Core #8 Boxberger
Russell Co., Ks.
W/2 NW/4 NE/4 Sec. 26-14S-14W
ELEVATION: 1800 KB

CORE DESCRIPTION

Core #3 3126-3144 Full recovery

3126-26 $\frac{1}{2}$	SH. DR. GRY.
3126 $\frac{1}{2}$ -31 $\frac{1}{2}$	LS. F. X. DSE.
3131 $\frac{1}{2}$ -32	LS. F. X. DSE.
3132-35	LS. THIN SH. LAM.
3135-39	LS. PT. FOSIL. MOSTLY F. X. DSE. P. SCAT. VUG. POROSITY IN FEW SPOTS (40% SATR. 36-38)
3139-44	LS. DSE. SH. LAM.