

24. 14. 14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.  
Farm- Ebel "A" No. 8-W

SEC. 24 T. 14 R. 14W  
NE NE SW  
330' S & 330' W of Center

Total Depth. 3130' PB 3118'  
Comm. 12-12-59 Comp. 12-30-59  
Shot or Treated.  
Contractor. Barbour Drlg. Co.  
Issued. 3-4-61

County Russell  
KANSAS



Elevation. 1743' Gr.

Production. Waterflood Input Well

CASING:

8 5/8" 740' cem w/500 sx.  
5 1/2" 3129' cem w/150 sx.  
DV tool @ 2326' cem w/125 sx.

Figures Indicate Bottom of Formations.

lime	50
shale	290
shale & sand	350
shale	365
shale & red bed	705
red bed	715
Anhydrite	760
shale & shells	1050
shale	1400
lime & shale	1810
lime	1940
lime & shale	2050
shale & lime	2175
shale	2250
cored shale & sand	2300 (rec. 50')
cored shale & lime	2318 (rec. 18')
shale & shells	2385
shale & lime	2535
lime & shale	2565
shale	2585
lime	2650
lime & shale	2685
lime	2830
cored shale & lime	2880 (rec. 50')
Cored lime & shale	2930 (rec. 50')
cored lime	2980 (rec. 50')
cored lime	3030 (rec. 50')
cored lime & shale	3080 (rec. 50')
cored lime & shale	3130 (rec. 50')

Total Depth  
Plugged back to 3118'

TOPS:

Tarkio Sand	2261
Topeka	2585
Heebner	2817
Dodge	2833
Lansing	2879
Base Kansas City	3089

39 shots 3050-60  
66 shots 2976-92  
33 shots 2966-74  
9 shots 2961-63  
31 shots 2917-25  
25 shots 2900-06  
44 shots 2880-91

1040' fluid in 20 hrs.