


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - COOPERATIVE REFINING ASS'N.
Farm - Reinhardt "B" No. 5

SEC. 19 T. 14 S. 14W
NW NE SW

Total Depth. 3265
Comm. 12-30-49 Comp. 2-14-50
Shot or Treated.
Contractor.
Issued. 3-18-50

County. Russell
KANSAS



Elevation. 1849 (ind)

Production. 36 Bbls pr day, 15%
water.

CASING:

8 5/8" 875' cem w/450 sx.
5 1/2" 3258' cem w/125 sx.

Figures Indicate Bottom of Formations.

soil, post rock	55
shale	250
shale, shells	450
sand	505
shale, red bed	671
anhydrite	890
shale, shells	1280
salt	1485
lime brkn, shale	1780
lime	2005
lime, shale	2070
lime shells, shale	2295
shale, shells	2385
shale	2515
shale, shells	2660
lime, shale	2840
lime	3262
3262 RTD = 3260 DF	
lime	3265
Total depth	

Tops:
Heebner 2956
Toronto 2974
Lansing 3014
Reagan 3258

Completion Data:

At. R.T.D. 3260, hole dry.
Drilled deeper 3262, bail test
10 gals oil pr hr.

Drilled deeper 3263 1/2, bail test
2 bbls oil pr hr.

Drilled deeper 3265, swbd down
and then swbd 4.67, 4.33, 5.33,
2.31, 7.26, 4.0, no water.