

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Plotted Texas CO.

Company - GULF OIL CORP.
Farm - Milton Reinhardt No. 3.

SEC. 19 T. 14 R. 14 W
CWN SE

Total Depth. 3271½'
Comm. 10-27-43 Comp. 12-10-43
Shot or Treated.
Contractor.
Issued. 2-5-44

County. Russell
KANSAS



CASING:
85/8" 668' Cem. II
51/2" 3264' Cem. II

Elevation. _____

Production. Pot. 68.04 BO
6.75 BW

Figures Indicate Bottom of Formations.

soil & sand	0-25
lime	40
lime, sand, iron	150 ✓
shale & iron	250 ✓
shale	310
shale & shells	465
sand	510
red bed, shale, shells	635
red bed	675
red bed & shells	870
anhydrite	920
shale & shells	1155
shale, shells, salt	1490
shale & shells	1580
shale & lime	1635
shale & shells	1650
sand & shale	1700
lime & shale	2700
lime	2987
lime & shale	3040
lime	3125
lime & shale	3180
lime brkn	3192
lime	3263
lime Arbuckle	3271½
Total Depth.	

Tops:
Topeka 2740
Lansing-K.C. 3025½
Arbuckle 3263

Acidized:
11-19-43 w/1000 Gals.
11-29-43 w/3000 Gals. thru
perforations 3025½-31½ &
3063½-69½