

34-14-14W

State Geological Survey
WICHITA, BRANCH

W E L L L O G

DATE COMMENCED: March 1, 1974
DATE COMPLETED: March 7, 1974

API# 15-167-20, 651

Louis M. Mai
LOUIE #2
SE/4 SE/4 SW/4
Section 34-T14S-R14W
Russell County, Kansas

ELEVATION: 1758 K.B.

FORMATION DATA

0 - 130' Clay & Sand
130 - 307' Shale & Sand Streaks
307 - 750' Shale & Red Bed
750 - 753' Red Bed
753 - 795' Anhydrite
795 - 955' Red Bed
955 - 1470' Shale
1470 - 1515' Shale & Lime streaks
1515 - 2067' Lime & Shale
2067 - 2658' Shale
2658 - 2890' Lime
2890 - 2894' Shale
2894 - 2909' Shale & Lime
2909 - 2922' Lime
2922 - 2952' Shale
2952 - 3185' Lime
3185 - 3214' Conglomerate
3214' RTD

ANHYDRITE	753'
TOPEKA	2658'
HEEBNER	2890'
TORONTO	2909'
DOUGLAS	2922'
KANSAS CITY	2952'
BASE K.C.	3185'
RTD	3214'

SURFACE PIPE: Set 8-5/8", used
28# casing at 307' with 200 sacks
common cement.

PRODUCTION CASING: Set used 5 1/2"
86 jts. of 17# casing, and 37 jts.
of 14# casing at 3195' with 125
sacks pozmix, 18% salt saturated
with Flowseal & C.F.R. 2 & 125
sacks pozmix-C.F.R.2.

A F F I D A V I T

STATE OF KANSAS]
COUNTY OF BARTON] ss.

Larry Curtis of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

described and sworn to before me this 11 day of March 1974.

My Comm. Expires:
April 11, 1974

Larry Curtis

Norothy M. Hague
Notary Public



State Geological Survey
WICHITA, BRANCH

34-14-14W

FORM C-2

STATE OF KANSAS
STATE CORPORATION COMMISSION - CONSERVATION DIVISION
3830 South Meridian - Box 17027
Wichita, Kansas 67217

DATA AND AFFIDAVIT

(On Cementing in Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137 and 55-138, 1947 Supplement to G. S. Kansas 1935)

API # 15-167-20,651

LEASE OWNER Louis M. Mai

OFFICE ADDRESS P. O. Box 33, Russell, Kansas 67665

LEASE NAME Louie WELL NO. 2 COUNTY Russell

(W)

EXACT SPOT LOCATION SE SE SW SEC. 34 TWP. 14 RGE. 14 (E)

CONTRACTOR Duke Drilling Co.

OFFICE ADDRESS Box 823 - Great Bend, Ks. 67530

Drilled with ~~(Cable)~~ (Rotary) tools: Date pipe set 3/1/74

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 12 1/4" Csg. (~~new~~) or (used) Size 8-5/8" 28#

Depth 307' Where set 307'

METHOD OF CEMENTING

Cement: Amount and kind 200 sacks common quick-set

Method: (By Service Co., Dump, Tog., etc.) Service Co.

Est. Height Cement behind pipe Circ.

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum 125'

Name of lowest fresh water producing stratum sand

Surface elevation of well same

ADDITIONAL INFORMATION

(Additional information may be submitted on separate sheet)

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS,

I, Larry Curtis, of the Duke Drilling Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.