

DRILLERS' WELL LOG

DATE COMMENCED: June 5, 1976
DATE COMPLETED: June 11, 1976

Louis M. Mai
LOUIE A-3
SW NW NW of Sec 34-T14-R14W
Russell County, Kansas

ELEVATION: 1783 K.B.

0 - 285'	Surface Soil, Shale, Post Rock & Sand Stks.	FORMATION TOPS
285 - 350'	Sand, Hard Streaks	
350 - 559'	Shale, Sand Streaks	Anhydrite 771
559 - 771'	Red Bed	Howard 2599
771 - 806'	Anhydrite	Severy 2641
806 - 1625'	Red Bed, Shale, Shells	Topeka 2661
1625 - 1820'	Shale, Lime	Heebner 2891
1820 - 2075'	Lime, Shale Streaks	Toronto 2910
2075 - 2599'	Lime and Shale	Douglas 2924
2599 - 2641'	Lime	Kansas City 2954
2641 - 2661'	Shale and Sand	Base K.C. 3186
2661 - 2891'	Lime	Granite Wash 3203
2891 - 2895'	Shale	RTD 3270
2895 - 2924'	Lime	
2924 - 2954'	Shale	
2954 - 3186'	Lime	
3186 - 3203'	Lime, Shale	
3203 - 3270'	Granite Wash	
3270'	RTD	

SURFACE PIPE:
Set new and used 8 5/8", 20# & 28#
pipe @ 558' w/285 sacks Common,
2% Gel, 3% cc.

PRODUCTION PIPE:
Ran used 14#, 5 1/2" casing @ 3269'
w/300 sacks 50/50 Pozmix w/18%
salt .75% CFB2 w/1/2 sack flo seal
pr. sack.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 21st day of June, 1976.

Clarence M. Hogue
Notary Public