

DATE COMMENCED: November 11, 1976  
DATE COMPLETED: November 17, 1976

Louis M. Mai  
LOUIE A-8  
NW NW NW  
Sec 34-T14-R14 W  
Russell County, Kansas

ELEVATION: 1780 K.B.

0 - 35'	Surface Soil, Shale, Post Rock
35 - 160'	Post Rock, Clay
160 - 766'	Red Bed, Shale
766 - 804'	Anhydrite
804 - 1515'	Shale, Lime, Shells
1515 - 1780'	Shale, Lime Streaks
1780 - 1930'	Lime, Shale
1930 - 2405'	Shale, Lime Streaks
2405 - 2635'	Lime and Shale
2635 - 2885'	Lime
2885 - 2889'	Shale
2889 - 2905'	Lime and Shale
2905 - 2916'	Lime
2916 - 2945'	Shale
2946 - 3184'	Lime
3184 - 3250'	Lime and Shale
3250'	RTD

FORMATION TOPS

Anhydrite	766
Severy	2635
Topeka	2653
Heebner	2885
Toronto	2905
Douglas	2916
Kansas City	2946
Base K.C.	3184
RTD	3250

SURFACE PIPE:

Set used 8 5/8", 28# pipe  
at 560' w/285 sacks Common,  
2% Gel, 3% cc.

PRODUCTION PIPE:

Ran used 14#, 5 1/2" casing  
at 3249' w/150 sacks 50/50 Pozmix  
w/18% salt and .75 CFR2

A F F I D A V I T

STATE OF KANSAS }  
COUNTY OF BARTON } ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 23rd day of November, 1976.

Kathleen M. Wagner  
Notary Public