

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **AYLWARD DRIG.**
 Farm- **Fink**

No. 1

SEC. 16 T. 14 R. 14W
E/2 SW SE

Total Depth. 3296
Comm. 6-1-65 Comp. 6-10-65
Shot or Treated.
Contractor. Aylward Drig.
Issued. 2-26-66

County Russell
KANSAS



CASING:

8" 0 880'
5 1/2" 0 3295' w/200 sx.
5 1/2" 1000' to surface w/284 sx.

Elevation. 1890' KB

Production. 8 BOPD

Figures Indicate Bottom of Formations.

surface clay	10
post rock	50
sand	30 80
shale	600
red bed	725
shale	882
anhydrite	918
shale & lime	1260
sh a l	1620
lime & shale	1925
lime	2222
shale	2425
shale & sand	2471
shale & lime	2588
shale	2750
lime w/shale breaks	2824
lime	2882
lime & shale	3029
shale	3045
lime	3219
lime & shale breaks	3293
Granite Wash	3296
Total Depth	

GEOLOGICAL TOPS:

Grand Haven Lime	2418
Dover Lime	2444
Tarkio Lime	2487
Elmont	2547
Howard	2694
Severy	2734
Topeka	2750
Heebner	2935
Toronto	3004
Douglas	3019
Lansing	3044
Granite Wash	3293

DST 3045-90' Open 90" Rec. 240' gas in pipe. 55' very sl. OCM, IBHP 168#/20"-FBHP 114#/30", FP 45-45#.

16-14-14W.



FINK #1 V

Casing Record: 5½" - 3295'
Company: Aylward Drilling Company
Contractor: Aylward Drilling Company
Commenced: June 1, 1965
Completed: June 10, 1965
Location: E½ SW SE 16-14-14W
Russell County
Kansas
Elevation: 1890 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	10	Geological Tops:
Post Rock	10	50	
Sand	50	80	Grand Haven Lime 2418
Shale	80	600	Dover Lime 2444
Red Bed	600	725	Tarkio Lime 2487
Shale	725	882	Elmont 2547
Anhydrite	882	918	Howard 2694
Shale & Lime	918	1260	Severy 2734
Shale	1260	1620	Topeka 2750
Lime & Shale	1620	1925	Heebner 2985
Lime	1925	2222	Toronto 3004
Shale	2222	2425	Douglas 3019
Shale & Sand	2425	2471	Lansing 3044
Shale & Lime	2471	2588	Granite Wash 3293
Shale	2588	2750	
Lime w/Shale Breaks	2750	2824	DST 3045-90 Open 90"
Lime	2824	2882	Rec. 240' gas in pipe, 55' very sl.0CM
Lime & Shale	2882	3029	IBHP 168#/20" - FBHP 114#/30"
Shale	3029	3045	FP 45-45#
Lime	3045	3219	
Lime & Shale Breaks	3219	3293	
Granite Wash	3293	3296 T.D.	Set 5½" casing @ 3295' w/200 sacks. Cemented 5½" from 1000' to surface w/284 sacks.

AUG 07 1965

State Geological Survey
WICHITA BRANCH

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Frank Hamlin

Subscribed and sworn to before me this 11th day of June, 1965

James D. ...