


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- COOPERATIVE REFINERY ASS'N.  
Farm- Fink "A" No. 1

SEC. 16 T. 14 R. 14W  
SE NW SE

Total Depth. 3316'  
Comm. 2-5-59 Comp. 2-14-59  
Shot or Treated.  
Contractor. Shields Drlg. Co.  
Issued. 6-27-59

County Russell  
KANSAS



Elevation. 1893'

Production. 5 BOPD

CASING:

8 5/8" 897' cem w/450 sx.  
5 1/2" 3314' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay, shale & shells	75
shale, shells, sand & redbed	800
shale and shells	887
Anhydrite	924
shale and shells	1565
shale and lime	1915
broken lime	2035
lime and shale	2230
shale and shells	2415
shale and lime	2820
lime	2915
lime and shale	3053
lime	3193
lime and shale	3295
granite wash & granite	3316 RTD
Total Depth	

TOPS: SCOUT	
Plattsmouth	2912
Heebner	2989
Lansing	3050
Granite Wash	3293