

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRIG.  
 Farm- Solbach "B" No. 1

SEC. 32 ~~1~~-T. 14 R. 14W  
 S $\frac{1}{2}$  s $\frac{1}{2}$  NE

Total Depth. 3170

Comm. 3-6-65

Comp. 3-17-65


County Russell

KANSAS

Shot or Treated.

Contractor. Co. Tools

Issued. 5-1-65



CASING:

8 5/8" 730' 400 sx.

Elevation. 1731' RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	50
shale & shells	215
sand	320
sand & shells	470
red bed	723
anhydrite	762
shale	1075
shale & shells	1285
shale	1450
lime & shale	2224
shale & shells	2335
lime & shale	2750
lime	2814
li e & shale	2928
lime	2962
lime & shale	3006
li e	3165
li e & lshale	3167
arbuckle	3170
RTD	

DST #9 3129-70' Op.30" rec 2200'S.wtr.BMR

DST #10 Straddle 2303-2433. Op.1. hr.  
 BHP 306#-252#,FP38-38.rec.60'mud.

BHP 43#-36#,FP 21#-32#20'.

TOPS: ~~Log~~

Tarkio	2315
Topeka	2629
Heebner	2856
Lansing	2915
Conglomerate	3144
Arbuckle	3167
TD	3170

DST #4 2926-62 Op.i hr. rec 270'gas,  
 30'OCM,180'WCM,BHP 745#-732#,FP 64#-140#

DST #5 2980'-3006' Op. 1hr.Wblow rec.  
 10'OCM & 50'WOCM.BHP 172#-162#,FP 43#-  
 54# in 20".

DST # 63066-90' Op.1 hr.rec.600'mud,  
 660' m.wtr.,w/gas BHP 812#-835#.

DST #7 3094-3147' Op 30" rec.1680'  
 mud.BHP 1020#-F.842#.

DST #8 3129-65' Op 30" rec. 9'mud,  
 FBHP 76#only. SI 20"

DST #1 2304-35. 20-20-40, wk:blow  
 thruout, rec.30' VSO & VCM,BHP 118#-  
 54#,FP 15#-21#.

DST#2 2774-2814 Op 40",rec.20'wtry.  
 mud,BHP 745#-669# FP 21#-32#,all in 20"

DST #3 2886-2931 Op.30" rec.5'mud **K**