

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas

Company - ALKAY OIL COMPANY  
Farm - Roxroat No. 1

SEC. 31 T. 14 R. 14W  
CML NE HW

Total Depth. 3162'  
Comm. 8-11-47 Comp. 8-23-47  
Shot or Treated.  
Contractor.  
Issued. 11-29-47

County. Russell  
KANSAS



CASING:  
10-3/4" 396' Cem. W/300 Sx.  
7" 3153' Cem. W/150 Sx.

Elevation. \_\_\_\_\_

Production. 35 Bbls.

Figures indicate Bottom of Formations.

surface clay	40
shale & shells	150
shale " sand shells	255
shale & shells	310
sand	330
shale & shells	350
sand	380
shale	400
red rock	745
anhydrite	770
lime & shale	1000
shale & shells	1190
salt & shells	1220
shale " shells	1300
salt	1425
lime & shale	1460
shale & shells	1550
lime & shale	1760
lime	1855
lime & shale	1955
lime	2070
shale & shells	2160
lime & shale	2180
lime	2210
lime & shale	2310
sand	2325
lime & shale	2495
shale	2595
lime & shale	2630
lime	2665
lime & shale	2685
lime	2845
lime & shale	2862
shale	2879
lime white, hrd	2882
lime sft. fair sat.	2885
lime white	2894
red rock & shale	2910
lime sft slight sat.	2917
lime & shale	2938
lime good sat & por.	2942
lime	2948
lime slight sat.	2953
lime white, hard	2973
lime red & green shale	2983
lime stain	2986
lime & shale	2994
lime hard stain	2997
lime Hard	3003
lime wh sft stain	
porous. Water	3017
lime hard	3055
lime fairly hrd,	
oolitic.	3065
spotted stain & porosity	
lime & shale	3145
conglomerate	3154
dolomite Good sat.	3162

Total Depth 3162'

Drilled plug - filled up 2800'  
oil in 24 hours.

TOPS:

Topeka	2630
Dodge	2879
Kansas City	2910
Arbuckle	3154