


CITIES SERVICE OIL.
 Strecker No. 1C.

SEC. 36 T. 14 R. 14W
 NE NW SW
 330'S 982'E of W/4 Cor.

Total Depth. 3153' P.B. 2951'
 Comm. 7-20-37 Comp. 8-28-37
 Shot or Treated, 5000 Gals.
 Contractor. J.E.Mabee Drlg.Co.
 Issued. 11-20-37

County. Russell



Elevation.

CASING:
 12 $\frac{1}{2}$ " 348'
 8 $\frac{1}{4}$ " 2928'

Production. Pot. 363' B.

Figures Indicate Bottom of Formations. 12% wtr after acid.

sand & shells	100	Top Oswald 2905
post rock	175	Top oolitic zone 2935-41
post rock & shale	250	Top Granite wash 3130
iron	325	Pen 23'
shale & shells	357	T.D. 3153
shells & iron	398	
red bed & shale	618	
red beds	700	
shale & shells	725	
anhydrite & lime hrd	758	
shale & salt	1012	
shale & shells	1150	
salt	1179	
salt & shells	1310	
shale & shells	1440	
lime & shale	1704	
brkn lime	1774	
lime	1824	
brkn lime	1880	
lime	2046	
lime & shale	2380	
brkn lime	2432	
lime & shale	2543	
lime	2642	
lime hrd	2662	
limo & shale	2750	
lime	2890	
limo & shale	2895	
cored lime	2930	
sm sh oil & gas 2907-09		
SIM 2930-2928		
Oswald lime	3001	
lime wtr at 3000	3035	
lime	3045	
shale	3055	
lime	3070	
shale	3075	
lime	3095	
shale	3100	
lime	3125	
slate	3130	
lime	3135	
granite wash	3153	
Total Depth.		

Plugged back 2951'