


STANOLIND OIL & GAS CO.
Frederich Michel No. 1-B.

SEC. 36 T. 14 R. 14W
CWL NW NW
1980' N SL 330' E WL NW $\frac{1}{4}$

Total Depth. 3156'
Comm. 11-18-39 Comp. 1-2-40
Shot or Treated.
Contractor.
Issued. 2-3-40 Cable 3156

County. Russell



CASING:
20" 61'
13" 512.22'
7" 3145.39'

Elevation.

Production. Pot. 770 B.

Figures Indicate Bottom of Formations.

No wtr

cellar	8	red rock	1860	lime hrd-cored	2967
sand	45	lime wh	1885	sm sh oil 2959-60	
shale	50	shale brown	1898	shale blue-cored	2969
shale sdy	60	shale blue	1925	lime hrd-cored	2981
shale yellow	70	lime	1940	shale sft-cored	2985
sand 5 BW	90	shale gy	1955	lime sft-cored, sh oil	2987
shale	115	lime	1980	lime hrd-cored	2999
sand 15 BW	145	shale red	2000	lime sft-cored	3004
shale	160	lime	2025	HFV 2999-3004	
shale blue HFV 170-90	170	shale blue	2045	lime brown sft	3020
shale brown	205	shale red	2055	lime	3064
sand white mixed w/		lime	2060	shale blue	3066
iron	215	shale red	2070	lime	3081
shale	242	lime LBW 2075	2086	shale blue	3084
iron	246	shale brown	2095	lime	3102
shale	255	lime sdy	2105	shale blue	3118
lime	275	lime	2110	lime	3137
shale	290	shale blue	2120	shale blue	3143
lime sdy	295	lime	2145	lime	3152
shale blue	325	shale blue	2155	lime sft-sh oil	3156
sand	335	lime	2195	Total Depth.	
shale	360	shale blue	2215		
shale blue	370	lime	2230		
sand	395	shale blue	2235	Top Basal Sand 3153	
shale blue	405	lime	2240		
sand	415	shale blue	2245	lime-sh oil & gas 2282-	
red rock & shale	735	lime	2250	2305	
anhydrite lime	768	shale brown	2265	lime porous-oil 2928-2932	
red rock LBWPH 775	925	lime	2277	lime porous-oil 2941-48	
shale blue	960	shale red	2280	lime hrd-sh oil 2959-60	
red rock	1025	lime LBOPH 2282-90	2310	lime sft-sh oil 2985-87	
shale blue	1040	sh gas 2300-2305		lime sft-sh oil 3152-56	
red rock	1055	shale blue	2340		
shale blue	1075	lime	2357	Potential of 770 B0, no wtr	
shale brown	1093	shale red	2380	8 hr-physical test 256.56	
lime	1098	shale blue	2402		
shale gy	1103	lime	2415		
lime	1105	shale blue	2425		
shale gy	1112	lime	2430		
salt	1415	shale blue	2455		
shale blue	1420	lime	2470		
lime	1430	shale blue	2475		
shale blue	1440	lime	2485		
lime	1465	shale blue	2502		
shale blue	1475	lime	2507		
lime	1480	shale blue	2540		
shale blue	1485	lime	2565		
lime	1506	shale blue	2575		
shale blue	1515	lime	2590		
shale red	1535	shale blue	2606		
lime	1565	lime $\frac{1}{2}$ BWPH 2809-15	2835		
shale sdy	1590	shale blue	2845		
lime	1615	lime	2865		
shale brown	1646	shale red	2890		
lime	1715	shale blue	2898		
shale blue	1735	Kansas City-Lansing lime	2918		
lime	1772	shale - cored	2922		
shale blue	1780	lime - cored	2928		
shale brown	1788	lime porous-cored (oil)	2932		
lime	1800	lime - cored	2941		
shale brown	1810	lime porous - cored (oil)	2948		
lime white	1845	lime hrd cored	2957		