

July, 1942

Central, # 1 Chrisman
SW NW NE, 20-14S-14W
Elev. 1872' *PL* P

Cable tools

Pennsylvanian Conglomerate 3277'-3333'

- 3277-3296 Interbedded gray shale and thin limestones, the latter with a few included sand grains.
- 3296-3325 Limestone, light buff to white, spotted pink and red with abundant included coarse round sand grains, angular quartz fragments, fresh pink feldspar, and fresh biotite. Red shaly partings.
- 3325-3328 Red to purple clay including sand grains as below and gradational into
- 3328-3333 Conglomerate of coarse sand, both rounded and angular with black inclusions, and rare chert fragments.

Arbuckle Top 3333' Penetration 2' Subsea -1461'

- 3333-3335 TD Sand, medium, rounded, with rare worn pink feldspar grains; in part silicified into quartzite with hazy oolites, solid or hollow. Boyce.

Remarks: Estimated restored top of Pre Cotter at 3248' or Subsea -1376' E

ML & RFW