

July, 1942

Hartman & Blair, # 2 Gurney
NW NE NW, 23-14S-14W
Elev. 1818'

Cable tools
Lansing producer

Pennsylvanian Conglomerate 3210'-3221'

3210-3221 Marine limestone, white to pink, with imbedded coarse round sand grains, rare very coarse fresh feldspar fragment, and occasional granite pebble. Basal foot or 6" of conglomerate of rounded fresh granite pebbles, lime coated.

Pre Cambrian Top 3221' Penetration 81' Subsea -1403'

3221-3290 Fresh pink biotite granite.
3290-3302 No samples.

RFW & ML