

July, 1942

1. Cities Service, # B-3 Strecker
COW $\frac{1}{2}$ SW NE, 36-14S-14W
Elev. 1750'

Cable tools below 3150' equals
3152' corr.

Pennsylvanian Conglomerate 3142'-3152'

3142-3149 Buff to white marine limestone with abundant
included sand grains, in part well rounded
derived from the basal Arbuckle and in part
coarse angular pitted grains from the Pre Camb.
3149-3152 Conglomerate of coarse sand and quartzite frag-
ments. Quartzite is granular, friable, and
includes muscovite books. Some adhering fine
recrystallized sand grains reworked from the
Everleigh-Reagan.

Pre Cambrian Top 3152' Penetration 8'

Subsea -1402'

3152-3157 Weathered granite. Feldspars are altered to
white clay. Biotite is in part altered to
chlorite. Coarse pitted quartz grains. No
porosity.

3157-3160 TD Slightly weathered granite. Abundant salmon
feldspar only partially altered; fresh biotite.

Remarks: Small producer from the conglomerate--initial production of
113 bbls oil and 1% water.
