

July, 1942

Stanblind, # B-3 Michel
C S $\frac{1}{2}$ N $\frac{1}{2}$ NW, 36-14S-14W
Elev. 1764'

Cable tools 3152' equals 3155'

Pennsylvanian Conglomerate 3146'-3153'

3146-3153 Foot or two of sandy limestone grading into conglomerate of coarse sand grains with black inclusions derived from the Pre Cambrian, friable quartzite fragments, medium sand from the Arbuckle, and rare granite fragments. Upper part limy; some porosity in lower part.

Arbuckle Top 3153' Penetration 6' Subsea -1389'

3153-3155 Sand, friable clusters of very coarse sand grains, faceted, with adhering recrystallized fine and medium grains, oilstained. Loose recrystallized fine and medium sand. *Evenly distributed*

3155-3159 TD No samples.

RFW & ML