


STANOLIND OIL & GAS CO.
A.H.Witt No. 3.

SEC. 10 T. 14 R. 16W
OW 1/2 NE SW
1980' N SL 1650' E WL SW 1/4

Total Depth. 3296' PB 3071'
Comm. 3-17-40 Comp. 5-2-40
Shot or Treated.
Contractor.
Issued. 6-29-40 Rotary 3296

County. Russell



CASING:
8 5/8" 623'
5 1/2" 3039'

Elevation.

Production. Pot. 26 B.
65 EW

Figures Indicate Bottom of Formations.

cellar 8
shale & lime 60
sand 70
shale & shells 240
shale & lime 435
sand 515
shale & lime 625
shale red 865
anhydrite lime 895
shale red 925
shale & shells 1210
shale & salt 1510
salt 1560
shale & shells 1825
lime 1895
lime sdy 1990
lime brkn 2335
shale & shells 2430
shale 2730
Core #1 10'/10' 2740
rec. 1'8" shale
8'4" lime hrd
Core #2 18'/20' 2760
rec. 15' shale w/lime
strks & 3' lime w/very
little shale
sh oil 2757-60
lime blue 2925
shale 2955
lime 3015
Core #3 13'7"/20' 3035
rec. 10'7" shale & 3'
lime w/slight sh oil
Core #4 17'6"/20' 3055
rec. 2' lime, 3' shaley
lime, 5' shale, 4'6" lime
w/sh oil, & 3' lime
oil show 3047'6" to 3052
Core #5 14'/15' 3077
rec. 1'6" hrd dry lime
7' porous lime w/good
oil show, 3' lime hrd
gy & 2'6" lime porous
good oil shows 3057-62
& 3066-70
Core #6 7'/20' 3090
rec. 1'6" lime hrd dry
3'6" lime porous w/sh
oil & 2' lime hrd dry gy
sh oil 3084-88
Core #7 13'/15' 3105
rec. 13' hd gy lime w/
scattered shale strks
lime 3190
shale & lime 3250
Core #8 15'/15' 3265
Core description:
shale gy to
greenish 3250- 3254
limestone tan med.
cryst 3254- 3258

shale green 3258-3259
shale red 3259-3262
lime brown to gy conglomeratic
w/slight sh of oil 3262-3263
granite wash weathered
granitic material & also
weathered schist
Core #9 7'/7' 3265-3270
rec. 7' granite wash
Core #10 14'/18' 3272-3290
rec. 14' granite wash
weathered granitic &
schistose material
Core #11 4'6"/6' 3290-3296
rec. 4'6" granite wash
Total Depth.

No commercial pays encountered,
plugged back to 3150 w/cement
When tubing was run to plug
back to 3150, tubing froze in
hole & was cut off at 3048
w/Acme Tool Cutter, leaving
101' of 2 1/2" tubing in hole.
Drilled by tubing to P.D.3071

Plug back depth 3071

Anhydrite lime 865-95
Topeka lime-sh oil 2757-60
3047'6" to 3052
Kansas City-sh oil 3057-3062
3066-3070

Potential of 26 oil 65 wtr,
24 hr pwab test thru 5 1/2" casing.
12-hr pumping test after head
off 2 1/2" oil 7 1/2" wtr