


A. H. WITT  
Fee No. 1-B.

SEC. 10 T. 14 R. 15W  
SE SW SW

Total Depth. 3250' PB 3240  
Comm. 9-7-39 Comp. 10-17-39  
Shot or Treated.  
Contractor.  
Issued. 12-23-39

County. Russell



CASING: 8" 2708'  
15 1/2" 327' 5" 3201'  
12 3/4" 592'  
10" 864'

Elevation.

Production. Pot. 169 B.

Figures Indicate Bottom of Formations.

rock & shale	30	shale brown	2195	Top Salt 1243
shale blue	170	lime	2205	Top Topeka 2712
red rock	255	shale blue	2212	
shale wh	265	lime, shells, shale	2230	
sand HFW 307	307	lime brkn	2252	
shale blue	350	shale brkn, shells	2275	
sand HFW 360	360	lime	2285	
shale blue	435	shale blue, shells	2387	
shale blk	445	gas sand, gas 2387-95	2395	
shale blue	455	shale blue	2450	
sand	488	lime brkn	2472	
red rock	855	shale blue	2500	
chalk	864	lime	2518	
lime, anhydrite	869	shale blue	2540	
lime	918	lime	2575	
shale brown, lime		shale blue	2580	
shells	975	lime, shells, shale	2615	
shale red	1030	shale blue, shells	2680	
red rock	1062	little lime	2705	
shale & shells	1108	shale blue	2716	
shale brown	1150	lime	2734	
shale blue	1250	shale blue	2739	
salt	1522	lime	2863	
shale blue, shells	1545	shale blue	2866	
lime	1560	lime LBWPH 2902-15	2902	
shale & shells	1570	sdv lime	2935	
lime	1590	lime	2955	
shale blue	1625	shale blue	2959	
shale gy	1635	lime brkn	2975	
shale brown	1645	shale blue	2980	
lime	1652	shale brown	2991	
shale brown	1660	shale blue, shells	2997	
lime	1665	lime	3080	
shale blue	1675	LBOPH 3020-25		
lime	1690	sdv lime	3133	
shale & shells	1720	shale blue	3138	
lime	1745	lime	3162	
B. shale & shells	1780	shale brown	3170	
shale blue	1790	lime	3195	
lime	1810	shale blue, shells	3200	
shale gy	1820	lime	3219	
lime brkn	1850	shale blue	3223	
shale blue	1875	lime	3227	
lime	1895	shale, shells	3230	
shale brown	1925	lime, sh oil	3232	
shale blue	1935	lime, sm inc in oil	3233	
lime, shells, shale	1945	lime, sm inc in oil	3234	
lime	1965	shale blue, shells	3238	
blue shale, shells	1990	shale varicolored	3240	
lime	2020	conglomerate	3246	
shale blue	2030	granite	3250	
lime	2045	Total Depth.		
shale brown	2070			
lime	2080	Plugged back to 3240		
shale & lime shells	2090			
lime hrd	2095	Pipe underreamed to 3229,		
shale gy	2105	and cemented.		
red rock	2115	Shot w/Lane-Wells gun-		
lime	2138	perforator:		
shale blue	2145	36 holes in open hole, between		
lime	2160	3236-3229		
br. shale, shells	2175	60 shots from 3219-3226		
lime	2190			