


WOLF CREEK OIL CO.
Witt No. 1.

SEC. 10 T. 14 R. 15W
NE SE SW

Total Depth. 3266'
Comm. 6-16-38 Comp. 7-28-38
Contractor.
Shot or Treated.
Issued. 8-27-38

AUG 27 1938

County. Russell



CASING:
12 1/2" 549' 7" 3107' UR 3174 &
10 " 892' UR 3262'
8 1/4" 2489'

Elevation.

Production. Pot. 2410 Bbls.

Figures Indicate Bottom of Formations.

shale yellow	40	lime	1625	shale cave	2460
shale blue	125	shale blue	1635	shale blue	2475
shale sdy	155	red rock	1685	lime cave	2495
shale lgt	200	shale blue	1705	shale	2510
shale brown	220	shale lgt	1720	shale blue&shells cave	2535
shale lgt	235	shale brown	1725	shale blue cave	2550
sand HFW	320	shale blue	1735	lime cave	2585
shale blue	350	lime	1760	shale blue	2600
sand	365	shale blue	1775	lime	2610
shale blue HFW	420	shale red	1800	shale	2645
shale brown	430	lime	1830	shale blue&shells cave	2705
shale blue	450	shale	1840	lime	2835
sand	490	lime	1860	shale	2838
shale red sdy	495	shale	1865	lime	2845
shale sdy	520	lime	1930	shale	2847
redrock	525	shale grey	1960	lime	2870
shale red	542	shale	1970	shale	2875
redrock	550	lime	1990	lime	2975
sand HFW	565	slate blue	2000	shale blue	2985
red rock	640	shale blue	2015	lime	3000
shale red	675	lime	2040	shale blue	3005
red rock	755	shale blue	2050	shale red	3010
shale red	800	shale red	2070	shale shells	3025
red rock	845	shale sdy	2095	green shale & O.S.lime	3029
shale red	875	lime	2105	lime	3040
chalk	882	shale	2125	shale blue	3045
lime	920	shale red	2140	lime	3110
shale red	1030	red rock cave	2155	sdv lime	3120
red rock	1085	shale lgt	2170	lime	3150
shale blue	1115	lime	2185	brkn lime	3160
shale red	1175	red rock	2215	lime	3195
red rock	1220	shale shells	2245	shale red & blue	3197
shale red	1230	lime	2255	lime	3205
shale grey	1260	shale blue & shells	2280	lime brkn	3210
slate shells	1280	slate shells	2305	lime	3220
slate salt	1305	shale blue & shells	2330	blue, red, shale & lime	3226
salt	1465	shale blue cave	2350	blue shale & shells	3233
lime & salt	1515	shale	2360	lime	3247
salt	1545	lime	2370	shale	3250
shale blue	1575	shale	2375	lime	3260
slate blue	1585	shale blue & shells	2405	shale blue	3268
slate shells	1610	shale blue	2430	sand Gorham	3266

Total Depth.

Oil Shows:
3175-3180