

KANSAS

State Geological Survey
WICHITA BRANCHWELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 167 — 01684
County Number

Operator

Crude Producers, Inc.

Address

P.O. Box 55 Russell, Kansas 67665

Well No.

#2

Lease Name

Sander

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Revlin Drig., Inc.

Geologist

Jim Norris

None

Spud Date

Re-entry 7-14-80

Date Completed

7-17-80

Total Depth

3417'

P.B.T.D.


Directional Deviation

Oil and/or Gas Purchaser

S. 9 T. 14 R. 15 E W

Loc. 3/2 SW NE

County Russell

640 Acres
N

Locate well correctly

Elev.: Gr.

DF KB 1859' K.B.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
REENTRY	12 1/4	8 5/8	28"	585			
Production	7 7/8	5 1/2	14#	3352'	60-40 Poz-Mix	150	4% Gilsomite 2% gel 3/4 of 1% GFR2 10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			
2 7/8	3275				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production <i>Aug 1980</i>		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil <i>5</i> bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) <i>no other info. Released</i>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Crude Producers, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. #2	Lease Name Sander		Dry Hole
S <u>9</u> T <u>14</u> R <u>15</u> E <u>W</u>			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Sand & Shale	0	195	
Shale & Shells	195	285	
Sand	285	310	
Shale & Shells	310	465	
Sand & Red Bed	465	560	
Shale & Shells	560	587	
Red Rock-Shale & Shells	587	725	
Red Bed-Shale & Sand	725	893	
Anhydrite	893	927	
Shale & Shells	927	1655	
Lime	1655	1945	
Lime & Sand	1945	2000	
Shale	2000	2155	
Shale & Lime	2155	2802	
Lime	2802	2970	
Shale & Lime	2970	3020	
Lime - K.C.	3020	3027	
Lime & Shale	3027	3066	
Lime	3066	3120	
Lime Re-Entry	3117	3180	
Lime	3180	3280	
Dolomite	3280	3335	
Arbuckle - Granet wash	3335	3400	
Granet - wash	3400	3417	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>Paula J. Gibson</i> Signature Bookkeeper Revlin Drlg., Inc. Title July 18, 1980 Date		